



Transworld Furtech Pvt. Ltd.

Survey No. 39/1 & 39/2 MIDC, Dhatav, Roha
 District- Raigad - 402 109, Maharashtra
 Tel. No. +91 2194 264492 Fax +91 2194 263392 E-Mail: purchase.roha@transfurl.com

WORK ORDER

W.O. NO: TFPL/Roha/EOU/WO/21-22/114/A

M/s. Utkrshita Infracore Private Limited Pune.
 Shop B-10, Mantri Park, Near Natraj Gas Agency, Kothrud, Pune-38

DATE: 25th MARCH 2022
 INDENT NO: DATE:
 Comp.No. DATE:
 QUOTE NO:
 DATE: 25th MARCH 2022

Kind Attn: Mr. L.k. Deshpande (9867186048)

We are pleased to place order for CIVIL Work as per details and terms & conditions mentioned below.

Sr. No	Descriptions	Unit	Rate (Rs)
CIVIL WORK AT SOP PLANT			
1	Excavation in all kind of soil upto 1.5 meter depth by Machine with excavated material shifting & stacking as directed by client engineer upto 50 m.	Cu.m	240.00
2	Excavation in soil, murrum, hard murrum by machine from 1.5m to 3 m deep below plinth including shifting the soil but excluding dewatering.	Cu.m	300.00
3	Excavation in soil & soft Murrum w/o Back filling (MANUAL) up to 1.5m depth with excavated material shifting & stacking as directed by clients Engineer upto 50m etc.	Cu.m	700.00
4	Excavation in soil & hard Murrum w/o Back filling (MANUAL) up to 1.5m depth with excavated material shifting & stacking as directed by clients Engineer upto 50m etc.	Cu.m	1200.00
5	Dewatering with pump with male coolie	Hour	1600.00
6	Backfilling of excavated earth which is stacking around excavation area.	Cu.m	120.00
7	Backfilling with supply of Murum with compaction etc.	Cu.m	600.00
8	Murrum filling from Site with shifting murum from stacking place upto 50m by machine etc.	Cu.m	169.00
9	Providing & laying 230mm Dry Rubble soling including filling voids in the rubble & spreading murum on soling & compaction including shifting material from stacking place upto 50m etc.	Sq.m	340.00
10	RCC Work- Specially designed self flowing concrete using Neutrol 500 (admixture) + concrete laying including shifting material from stacking place upto 50m etc.	Cu.m	6165.00
11	M20 Grade.	Cu.m	6935.00
12	M25 Grade.	Cu.m	7280.00
13	M30 Grade.	Cu.m	
14	P/L PCC with shifting material from stacking place upto 50m	Cu.m	4200.00
15	M10	Cu.m	5350.00
16	M15	MT	114000.00
17	P/L Reinforcement Steel (FE 500)	kg	117.50
18	P/E Structural steel with shifting material from stacking place upto 50m etc.	Sq.m	505.00
19	P/L 50mm thick IPS flooring with shifting rabbit & stacking as directed by client engineer upto 50m etc.	Cu.m	6000.00
20	P/L BBK Masonry 230mm thk. (C.M 1:6) with shifting rabbit & stacking as directed by client engineer upto 50m etc.	Sq.m	470.00
21	P/L Sand faced plaster 20mm (single coat) - River Sand with shifting material from stacking place upto 50m etc.	Sq.m	450.00
22	Extra over for the additional thickness of Ext. plaster up to 30 mm with shifting material from stacking place upto 50m etc.	Sq.m	250.00
23	Extra over for the additional thickness of Int. plaster up to 15 mm with shifting material from stacking place upto 50m etc.	Sq.m	85.00
24	Hacking of old RCC structure- with shifting	Sq.m	558.00
25	MS Scaffolding	Sq.m	
26	Supply of Departmental labour	No	500.00
27	Male coolie	No	450.00
	Female coolie	No	1050.00
	Carpenter	No	1050.00
	Fitter	No	750.00
	Helper	No	1035.00
	Brick Mason	No	1400.00
	Plaster Mason	No	
28	Hire charges	Day	4950.00
	Air Compressure with RCC breaking without shifting rabbit.	Day	1675.00
	Electrical breaker with male coolie without shifting rabbit.	Hour	850.00
	JCB supply		
Demolition Items			
1	Breaking Concrete with cutting reinforcement steel & lifting debris w/o shifting	Cu.m	4200.00
2	Breaking Concrete w/o cutting reinforcement steel w/o shifting	Cu.m	3800.00
3	Demolition Brick Masonry work with shifting rabbit & stacking as directed by clients Engineer upto 50m etc.	Cu.m	2000.00
4	Demolition BB cota waterproofing with shifting rabbit & stacking upto 50m.	Cu.m	2250.00
5	Removing of Rubble soling with Rabbit shifting & stcking as directed by Clients Engineer upto 50m etc.	Sq.m	150.00
6	Breaking plaster with shifting rabbit & stacking as directed by clients Engineer upto 50m etc.	Sq.m	105.00

GSTIN No.: 27AACCT0972D1Z1

CIN: U51497MH2004PTC148832

TERMS AND CONDITIONS:

- TAXES: GST extra as applicable
- PAYMENT: After submission of Approved Bill
- COMPLETION PERIOD:
- REMARKS:

Prepared By:

for TRANSWORLD FURTECH PVT. LTD.

Dept Head:

AUTHORISED SIGNATORY

Regd. Office:

No.: 1801, 18th Floor, The Affaires Building, Plot No.9, Sector-17, Sanpada, Navi Mumbai -400 705
 Tel: +91 22 2781 3100 Fax: +91 22 2781 5207 Email: purchase@transfurl.com



Transworld Furtech Pvt. Ltd.

Survey No. 39/1 & 39/2 MIDC, Dhatav, Roha
 District: Raigad - 402 109, Maharashtra
 Tel. No. +91 2194 264492 Fax: +91 2194 263392 E-Mail: purchase.roha@transfurt.com

WORK ORDER

M/S. Utkrushta Infracon Private Limited Pune.

Shop B-10, Mantri Park, Near Natraj Gas Agency, Kothrud, Pune-38

W.O. NO: TPPL/Roha/EOU/WO/21-22/114/B

DATE: 25th MARCH 2022

INDENT NO: DATE:

Comp.No: DATE:

QUOTE NO:

DATE: 25th MARCH 2022

Kind Attn.: Mr. L.k. Deshpande (9867186048)

We are pleased to place order for Civil Work as per details and terms & conditions mentioned below.

Sr. No	Descriptions	Unit	Rate (Rs) A Rate	Additional rate over A	Final Rate (Rs)
CIVIL WORK AT SOP PLANT					
1	Excavation in all kind of soil upto 1.5 meter depth by Machine with excavated material	Cu.m	240.00	0.00	240.00
2	Excavation in soil, murrum, hard murrum by machine from 1.5m to 3 m deep below plinth	Cu.m	300.00	0.00	300.00
3	Excavation in soil & soft Murrum w/o Back filling (MANUAL) up to 1.5m depth with	Cu.m	700.00	0.00	700.00
4	Excavation in soil & hard Murrum w/o Back filling (MANUAL) up to 1.5m depth with	Cu.m	1200.00	0.00	1200.00
5	Dewatering with pump with male coolie	Hour	1600.00	0.00	1600.00
6	Backfilling of excavated earth which is stacking around excavation area.	Cu.m	120.00	0.00	120.00
7	Backfilling with supply of Murrum with compaction etc.	Cu.m	600.00	0.00	600.00
8	Murrum filling from Site with shifting murrum from stacking place upto 50m by machine	Cu.m	169.00	6.00	175.00
9	Providing & laying 230mm Dry Rubble soling including filling voids in the rubble &	Sq.m	340.00	60.00	400.00
10	RCC Work- Specially designed self flowing concrete using Neutrol 500 (admixture) +				0.00
11	M20 Grade.	Cu.m	6165.00	0.00	6165.00
12	M25 Grade.	Cu.m	6935.00	0.00	6935.00
13	M30 Grade.	Cu.m	7280.00	0.00	7280.00
14	P/L PCC with shifting material from stacking place upto 50m				0.00
15	M10	Cu.m	4200.00	900.00	5100.00
16	M15	Cu.m	5350.00	0.00	5350.00
17					0.00
18	P/L Reinforcement Steel (FE 500)	MT	114000.00	0.00	114000.00
19	P/E Structural steel with shifting material from stacking place upto 50m etc.	kg	117.50	0.00	117.50
20	P/L 50mm thick IPS flooring with shifting rabbit & stacking as directed by client engineer	Sq.m	505.00	45.00	550.00
21	P/L BBk. Masonry 230mm thk. (C.M 1:6) with shifting rabbit & stacking as directed by client	Cu.m	6000.00	600.00	6600.00
22	P/L Sand faced plaster 20mm (single coat) - River Sand with shifting material from stacking	Sq.m	470.00	105.00	575.00
23	Extra over for the additional thickness of Ext. plaster up to 30 mm with shifting material	Sq.m	450.00	0.00	450.00
24	Extra over for the additional thickness of Int. plaster up to 15 mm with shifting material	Sq.m	250.00	0.00	250.00
25	Hacking of old RCC structure- with shifting	Sq.m	85.00	5.00	90.00
26	MS Scaffolding	Sq.m	558.00	0.00	558.00
27	Supply of Departmental labour				0.00
	Male coolie	No	500.00	75.00	575.00
	Female coolie	No	450.00	50.00	500.00
	Carpenter	No	1050.00	0.00	1050.00
	Fitter	No	1050.00	0.00	1050.00
	Helper	No	750.00	0.00	750.00
	Brick Mason	No	1035.00	0.00	1035.00
	Plaster Mason	No	1400.00	0.00	1400.00
28	Hire charges				0.00
	Air Compressor with RCC breaking without shifting rabbit.	Day	4950.00	0.00	4950.00
	Electrical breaker with male coolie without shifting rabbit.	Day	1675.00	0.00	1675.00
	JCB supply	Hour	850.00	100.00	950.00
Demolition Items					
1	Breaking Concrete with cutting reinforcement steel & lifting debris w/o shifting	Cu.m	3600.00	600	4200.00
2	Breaking Concrete w/o cutting reinforcement steel w/o shifting	Cu.m	3100.00	700	3800.00
3	Demolition Brick Masonry work with shifting rabbit & stacking as directed by clients Engineer upto 50m etc.	Cu.m	1800.00	200	2000.00
4	Breaking BB coba waterproofing with shifting rabbit & stacking upto 50m.	Cu.m	2250.00	0	2250.00
5	Removing of Rubble soling with Rabbit shifting & stacking as directed by Clients Engineer upto 50m etc.	Sq.m	100.00	50	150.00
6	Breaking plaster with shifting rabbit & stacking as directed by clients Engineer upto 50m etc.	Sq.m	57.50	47.5	105.00

GSTIN No.: 27AACCT0972D1Z1

CIN: U51497MH2004PTC148832

TERMS AND CONDITIONS:

1. TAXES:	GST extra as applicable
2. PAYMENT:	After submission of Approved Bill
3. COMPLETION PERIOD:	
4. REMARKS:	

Prepared By:

[Signature]

Dept Head:

for TRANSWORLD FURTECH PVT.LTD.

[Signature]
AUTHORISED SIGNATORY

Regd. Office: No. 1801, 18th Floor, The Affaires Building, Plot No.9, Sector-17, Sanpada, Navi Mumbai -400 705

Tel: +91 22 2781 3100 Fax: +91 22 2781 5207 Email: purchase@transfurt.com



Transworld Furtichem Pvt. Ltd.

Survey No 39/1 & 39/2 MIDC, Dhataw, Roha
District: Raigad - 402 109, Maharashtra
Tel. No. +91 2194 264492 Fax : +91 2194 263392 E-Mail: purchase.roha@transfurt.com

WORK ORDER

M/s. Utkrusshta Infracon Private Limited Pune.
Shop B-10, Mantri Park, Near Natraj Gas Agency, Kothrud, Pune-38

W.O. NO: TTPL/Roha/EOU/WO/21-22/114/C

DATE: 25th MARCH 2022
INDENT NO: DATE:
Comp.No. DATE:
QUOTE NO:
DATE: 25th MARCH 2022

Kind Attn.: Mr. L.k. Despande (9867186048)

We are pleased to place order for **Civil Retrofitting Work** as per details and terms & conditions mentioned below.


Sr. No	Descriptions	Unit	Final Rate (Rs)
CIVIL RETROFITTING WORK AT SOP PLANT			
1	Providing & Fixing 700 GSM Maxtreat-Glass fibre wrapping to columns in prescribed 1/2 wraps, inclusive of Primer & Putty. All the surface area will be measured including area of lapping.	Sq.m	2992.50
2	Providing & Fixing 700 GSM Maxtreat-Glass fibre wrapping to Beams in prescribed 1/2 wraps, inclusive of Primer & Putty. All the surface area will be measured including area of lapping.	Sq.m	3351.60
3	Providing & Fixing 700 GSM Maxtreat-Glass fibre wrapping to Slabs in prescribed 1/2 wraps, inclusive of Primer & Putty. All the surface area will be measured including area of lapping.	Sq.m	3531.15
4	Providing & Fixing 300 GSM Maxtreat-Glass fibre wrapping to columns in prescribed 1/2 wraps, inclusive of Primer & Putty. All the surface area will be measured including area of lapping.	Sq.m	1995.00
5	Providing & Fixing 300 GSM Maxtreat-Glass fibre wrapping to Beams in prescribed 1/2 wraps, inclusive of Primer & Putty. All the surface area will be measured including area of lapping.	Sq.m	2185.00
6	Providing & Fixing 300 GSM Maxtreat-Glass fibre wrapping to Slabs in prescribed 1/2 wraps, inclusive of Primer & Putty. All the surface area will be measured including area of lapping.	Sq.m	2403.50
7	Providing & Fixing 900 GSM Maxtreat-Glass fibre wrapping to Beams in prescribed 1/2 wraps, inclusive of Primer & Putty. All the surface area will be measured including area of lapping.	Sq.m	3724.00
8	Providing & Fixing 900 GSM Maxtreat-Glass fibre wrapping to Slabs in prescribed 1/2 wraps, inclusive of Primer & Putty. All the surface area will be measured including area of lapping.	Sq.m	3923.50
9	Surface preparation of Low Damaged columns for application of Glass Fiber wrapping after breaking plaster by grinding the surface & cleaning by air blower or water using booster pump.	Sq.m	85.00
10	Providing & applying BS 5F Polymer mortar for repairs & filling of small dents, pores, holes, broken edges, spalled concrete upto 1 inch depth, before application of Glass Fibrenet. Min. area of measurement will be 1mx1m.	Sq.m	1695.75
11	Providing & Laying BS 66 Microconcrete for the treatment of Beams-Beam sides & Bottom- from top after making holes in concrete at beam or slab top, poring BS66 in required consistency from one end to other assuring no vaccum including repairs to honey comb if any after deshuttering using T M Bond & BS 66 or B55F complete.	Cu.m	43320.00
12	Providing & Laying BS 66 Microconcrete for the treatment of Slabs- Bottom- from top after making holes in concrete at beam or slab top, poring BS66 in required consistency from one end to other assuring no vaccum including repairs to honey comb if any after deshuttering using T M Bond & BS 66 or B55F complete.	Cu.m	46075.00
13	MS Scaffolding	Sq.m	558.00
14	E/O increase in basic rate FOR Lead & Lift to all retrofit & civil work items beyond 50 m & ground floor @	%ge	15% per floor
15	Providing & Grouting the loose concrete of structural members to improve density of concrete using Maxgrout E10 in required proportion .	Nos/lit	1710.00

GSTIN No.: 27AACCT0972D1Z1

CIN: U51497MH2004PTC148832


TERMS AND CONDITIONS:

1. TAXES:	GST extra as applicable
2. PAYMENT:	After submission of Approved Bill
3. COMPLETION PERIOD:	
4. REMARKS:	

Prepared By: 

for TRANSWORLD FURTI CHEM PVT.LTD.

Dept Head:

AUTHORISED SIGNATORY 

Regd. Office:

No.: 1801, 18th Floor, The Affaires Building, Plot No.9, Sector-17, Sanpada, Navi Mumbai -400 705

Tel: +91 22 2781 3100 Fax: +91 22 2781 5207 Email: purchase@transfurt.com