

SH ELECTRICALS

- ◆ All type H.T./ L.T. Electrification → All Type A.C. / D.C. Motor Rewinding
- + All type Fabrication + All type M/c. Pannel Makers (M.C.C., P.C.C.)
- + Refirigation (m/c. A/c.) + Qualified Electrical Supply on Contract Basis
- + All Types Contol Pannel.

GSTIN: 27AHQPR6358F1ZP

Plot No. C - 113, Near Dhanvantari Hospital More Chowk, MIDC Walui, Aurangabad - 431 136. : 0240 2556216 Mobile: 9325147813, 9325147814,9325147811,9823189605, email smashgroup3@yahoo.in

To.

Method Statement

Kind Attan.:

Subject:

The functions & responsibilities of this committee are to:

- 1. Prior to the work, wear PPE's such as electrical safety shoes, helmet, goggles& gloves as per work requirement. It is also advice to place a fire extinguisher near the site during brazing or hot work.
- 2. Prepare all tools & equipment to be used before starting the worksuch as gas cylinder, gauge manifold, brazing set, brazing rod, flaring tool, spanner, wrench, screw driver, etc.
- 3. Remove the hazardous material from the area & barricade the area before staring the work.
- 4. Use LotoForTagout/Tagin before starting the work.
- 5. Check out whether power is off or not before touching the equipment.
- 6. Dismantle the equipment from the panel & then start the maintenance work.
- 7. After completing the work check the equipment that all parts will be connected properly.
- 8. If everything is ok then start the power & check the supply.
- 9. For height work wear proper PPE's such as safety belt, shoes, helmet & check ladder is in good condition or not, life line rope is there or not, if not available then firstly fix life line rope, assemble ladder, lock safety belt properly and then start the work



