

STANDARD OPERATING PROCEDURE OF KAESER COMPRESSOR

1 First of all before start compressor and dryer check all valves.

A Compressor Valve.



B Receiver Tank Valve.



C Dryer Valve.



D Filter Valve.



2 Check that it should be ON

3 Closed all BYPASS valves.

4 After dryer kept ON. & check the dryer due point maintain then switch ON compressor

5 After that take following reading of compressor and dryer at every 1 hour of interval

A Running Hrs - All Compressor

B Loading Hrs - All Compressor

C Individual compressor pressure - All compressor

D Temp. - All Compressor

E SAM- Pressure