

Project over view and Summery





➤ Background:-

Wall thickness veriation at Counter dia 14.0 mm in XF1C1 upper bracket

> Component details:-

As shown in image





> Following process analysis carried out

- Casting process mapping
- Buffing process mapping
- Machining process mapping



Root cause establishment (Why-why analisys)



WHY - WHY ANALYSIS

Step	Why-1	Why-2	Why-3	Why-4	Why-5
Occurrence	Wall thickness less due to machining shift	Machining reference taken from casting moving half.			
Out flow	Wall thickness not verified	No product knowledge	Lack of awareness	Lack of training	

Conclusion

Wall thickness getting shift due to Counter machining reference taken from moving half of casting.

Inspector not aware about wall thickness due to lack of training.



Countermeasure



Stage	Action	Trg date	Status
Occurrence	- Machining fixture modification done.	24/3/2023	Completed
Out flow	-Training given to inspector to verify wall thickness - Wall thickness verification added in hourly inspection report. -	24/3/2023 24/3/2023	

Proposed action


Stage	Proposed action	Trg date	Status
Occurrence	Outer wall thickness will be increase by 0.5 mm (for safer side)	24/3/2023	Completed



Training record



Training given to Inspector





Hourly inspection record



Wall thickness dimension added in hourly inspection report

HOURLY INSPECTION REPORT

Part no :- F2PD021070							Date : -														
Part Nar	Part Name :- XF-1D1 BRACKET														Shift:-						
Paramet ers	Width	Width	ø41.0 +0.02+0.12	ø41.0 +0.02+0.12	ø22 +0.140	ø28.0 +0.2	ø32.0 ^{+0.3}	Counter depth 5.0	ø14.0	M8x1.25 (6 no's)	M6x1.0 (3 no's)	ø6.647 /6.912	ø4.917 /5.153	Sliting 3.0 ±0.3		Wall 1.9	2.0 ±0.2				
613	20.5 ±0.2	16.0 ±0.2	10.0210.12	10.0210.22	+0.192	+0.2		deptil 3.0	5.0	(01103)	, 1103)	70.912	73.133	20.3	RELATION GAUGE	20.2	(2 Place)	REMARK			
Instrum ents	D.Vernier	D.Vernier	Bore Gauge	Bore Gauge	Plug Gauge	Plug Gauge	Plug Gauge	D.Vernier	D.Vernier	T.P.G	T.P.G	Pin Plug Gauge	Pin Plug Gauge	D.Vernier		D.Vernier	D.Vernier				
8:00																					
9:00																					
10:00																					
11:00																					
12:00																					
1:00																					
2:00																					
3:00																					
4:00																					
5:00																					
6:00																					
7:00																					

Operator Name& Sign :-

Part no	:- F2PD	021070												Date:-						
Part Name :- XF-1D1 BRACKET														Shift:-						
Paramet	Width	Width	ø41.0	ø41.0	ø22 +0.140	ø28.0	ø32.0 ^{+0.3}	Counter	ø14.0		M6x1.0 (3		ø4.917	Sliting 3.0		Wall 7.9	VERATICAL Wall 2.0 ±0.2			
ers	20.5 ±0.2	16.0 ±0.2	+0.02+0.12	+0.02+0.12	+0.192	+0.2		depth 5.0		(6 no's)	no's)	/6.912	/5.153	±0.3	RELATIONG AUGE	±0.2	(2 Place)	RE MARK		
Instrum ents	D.Vernier	D.Vernier	Bore Gauge	Bore Gauge	Plug Gauge	Plug Gauge	Plug Gauge	D.Vernier	D.Vernier	T.P.G	T.P.G	Pin Plug Gauge	Pin Plug Gauge	D.Vernier		D.Vernier	D.vermer	7		
8:00																				
9:00																				
10:00																				
11:00																				
12:00																				
1:00																				
2:00																				
3:00																				
4:00																				
5:00																				
6:00																				
7:00																				

Operator Name& Sign :-



Action Implemented



Outer wall thickness at defective area has been increase by 0.5 mm to avoid less wall thickness issue.







Thanks....